ATLANTIC CITY CONVENTION CENTER

JIM WHELAN BOARDWALK HALL

OVG OAK VIEW GROUP

TO: Proposal Responders

FROM: Clark Hughes

DATE: October 30, 2026

SUBJECT: ACCC STAIRWELL EGRESS CONTROL PLAN – GENERAL CONTRACTORS AS NEEDED ADDENDUM #4

RFI Responses

1. Please provide specific information for the cameras (ie Brand or equal, megapixels ,360degree quad camera, fisheye camera etc.) for each area to cover the desired location.
Refer to specification booklet 280000 and camera schedule for camera details. Minimum specs are provided, and contractor should provide a camera that meets specs and/or matches existing. (i.e. Hanwha or equal)

2. Please confirm that there is sufficient infrastructure and capacity existing in the building to facilitate the installation of the proposed cameras , or if the property will supply and install any additional equipment necessary if there is not capacity (ie IDFs MDF ect)
Existing IDFs have sufficient network to support all camera – no additional IDF capacity needed from contractor. Contractor to provide additional Genetec licensing and storage as required.

3. Who is providing, positioning, focusing, and mounting the cameras the note in the drawing says security and LV ?
Security contractor (under GC) to provide equipment, install and do final aim and focus, and programming of devices.

4-The new lever handles specified for the stairwell doors will not cover existing levers holes on single leaf doors. This will ultimately cause the door to lose its fire rating and may have to be replaced.
Provide alternate price to furnish and install a 90-minute replacement door to match existing, utilizing existing hardware. Paint to match. Identify the quantity of doors. Refer to the attached revised bid form.

END OF ADDENDUM #4

ATTH: Bid Form - Revised

Cc: Jim McDonald
Jason Resetar
Nicole Hagaman
Dan Iverson

"EXHIBIT G"

ADDENDUM #4

Schedule of Estimated Quantities, Unit Prices, and Lump Sum Items

Item	Description	Unit	Amount
1	Permits	L.S.	
2	Cost of Paint Materials and Labor	L.S.	
3	Cost of Cameras Material and Labor	L.S.	
4	Cost of Doors, Door Hardware Materials and Labor	L.S.	
5	Cost of Electric Materials and Labor	L.S	
6	Fire Alarm System Material and Labor	L.S.	
7	General Conditions	L.S.	
	TOTAL LUMP SUM	L.S.	

TOTAL LUMP SUM CONTRACT PRICE (Numerically) Line Item 1 through 7

_____

TOTAL LUMP SUM CONTRACT (In words) Line Items 1 through 7: _____

_____

_____

_____

_____**Dollars**

UNIT PRICE #1: The Bidder agrees to unit pricing for installation of one handle assembly on additional existing doors with panics on one side and nonfunctional trim opposite panic (show amount in both words and figures):

ADD **Per Door.**

$_____

UNIT PRICE #2: The Bidder agrees to unit pricing for door preparation for existing door with panic push side and no opposite side trim per door and new lever trim on opposite side of panic(show amount in both words and figures):

ADD **Per Door.**

$_____

UNIT PRICE #3: The Bidder agrees to unit pricing for installation of magnetic door closer, sensor, power supply and press to exit hardware on additional doors. Furnish and install 250′ cat 6 plenum rated cable with testing and terminations by contractor. Furnish and install a 20-amp, 120-volt feeder to include 150′ of #12 wire and 1 single pole breaker (show amount in both words and figures):

ADD _____ **Per Door.**

$_____

UNIT PRICE #4: The Bidder agrees to provide unit pricing for camera and installation. Furnish and install 1 250′ cat 6 plenum rated cable with testing and terminations by contractor. (show amount in both words and figures):

ADD _____ **Per Door.**

$_____

UNIT PRICE #5: Provide alternate price to furnish and install a 90-minute replacement door to match existing, utilizing existing hardware. Paint to match. Identify the quantity of doors with existing trim to be replaced where the specified replacement won't cover the previous hole.

ADD _____ Per Door.

$_____

ADDENDA: The Bidder acknowledges receipt of the following Addenda:

_____ Dated _____

_____ Dated _____

_____ Dated _____

Bidder Name: _____ Date: _____

By (print): _____

Signature: _____

Title: _____