

TO: Bid Responders

FROM: Clark Hughes

DATE: May 27, 2026

**SUBJECT: ACCC AUDIO SYSTEM UPGRADES – ADDENDUM #9**

**COMMENT:**

- 1. Addendum #8 - Alternate #4 - Bid Form, Line Item #14 - Removed from bid.**  
Due to the complexity of replacing the Hall A point source speakers, the owner has decided to eliminate this from the project entirely.
2. Refer to the attached revised Bid Form, Addendum #9
3. Bids will be received, opened, and read aloud in public at OVG offices at 2301 Boardwalk, Atlantic City, New Jersey on 5/29/26 at 11:00 a.m. eastern prevailing time. Administration Offices, Conference Room 160N.

ATTN: Revised Bid Form – Addendum #9

Cc: Jim McDonald  
Jason Resetar  
Nicole Hagaman  
Eric Taggart

**EXHIBIT G  
BID FORM**

**ADDENDUM #9**

*Schedule of Estimated Quantities, Unit Prices, and Lump Sum Items*

<b>Item</b>	<b>Description</b>	<b>Unit</b>	<b>Amount</b>
<b>1</b>	Permits		
<b>2</b>	Performance and Payment Bonds Surety	<b>L.S.</b>	
<b>3</b>	Mechanical HVAC Labor	<b>L.S.</b>	
<b>4</b>	Mechanical HVAC Material	<b>L.S.</b>	
<b>5</b>	Electrical Labor	<b>L.S.</b>	
<b>6</b>	Electrical Material	<b>L.S.</b>	
<b>7</b>	Audio Material (Base Bid)	<b>L.S.</b>	
<b>8</b>	Audio Labor (Base Bid)	<b>L.S.</b>	
<b>9</b>	Replacement of all Audio Speaker Backboxes ( <b>Base Bid</b> )	<b>L.S.</b>	
<b>10</b>	Attic Stock Speakers ( <b>Base Bid</b> )	<b>L.S.</b>	
<b>11</b>	<b>Alternate #1</b> - New Custom programming of system	<b>L.S.</b>	
<b>12</b>	<b>Alternate #2</b> - Itemized cost to replace individual amps/dsp	<b>L.S.</b>	
<b>13</b>	<b>Alternate #3</b> - Itemized cost to replace individual control panels with an event/meeting Room.	<b>L.S.</b>	
<b>14</b>	General Conditions	<b>L.S.</b>	
	<b>TOTAL LUMP SUM</b>		

**TOTAL LUMP SUM CONTRACT PRICE (Numerically) Line Items #1 through #15**

\_\_\_\_\_ Dollars

**TOTAL LUMP SUM CONTRACT (In words) Line Items #1 through #15**

\_\_\_\_\_  
\_\_\_\_\_ Dollars

**ADDENDA:** The Bidder acknowledges receipt of the following Addenda:

- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_
- \_\_\_\_\_ Dated \_\_\_\_\_

Bidder Name: \_\_\_\_\_

Date: \_\_\_\_\_

By (print): \_\_\_\_\_

Signature: \_\_\_\_\_

Title: \_\_\_\_\_

## **ADDENDUM #9**

### **Added Base Bid Items #9 & #10 & Alternates #1 through #4 – Scope of Work**

#### **Added Base Bid**

1. **Added Base Bid – Line item #9**

Respondents shall provide a separate line-item cost within their base bid for the material and labor to replace the back boxes for all recessed ceiling loudspeakers. The contractor shall be responsible for coordinating existing ceiling elements and preserving the integrity of ceiling tiles and any other elements and replace damaged tiles as required.

2. **Added Base Bid – Line Item #10**

Respondents shall provide within their base bid a quantity of (10) 8” speakers with backboxes and (10) 12” speakers with backboxes for owner stock.

#### **Alternates**

1. **Alternate #1 – Line Item #11**

Bid respondents shall provide a separate line-item cost to perform professional reprogramming and advanced customization of the primary head-end audio control system. This scope is distinct from the base bid reprogramming required for a functional system and focuses on an owner coordinated tailor user experience, ease of use and operational flexibility and shall include a Varia 15.6” Touch Screen Control panel including installation within the existing rack room with full audio routing and control capabilities (exact mounting location of new touch screen to be coordinated with owner in field). This control programming shall also be applied to the main control computer next to the racks. Respondents shall allow for (1) programmers for (5) working days working along with an owner representative within their bid for the required programming and customization.

2. **Alternate #2 – Line Item #12:**

Bid Respondents shall provide an itemized cost for the material and labor required for the replacement of an individual Amplifier or DSP unit within the existing audio rack. The owner at their discretion will add additional or subtract from the base bid based upon this itemized cost.

3. **Alternate #3 – Line Item #13**

Bid Respondents shall provide an itemized cost for the material and labor required to furnish and install a Vario 10.1” Touch Panel within an Event and/or Meeting room

located at the existing control panel locations noted on the AV drawings. Pricing shall include factory terminated patch cable connection to the F/UTP category cable connection point provided in the ceiling by the section 271000 scope of work in the contract documents. Retrofit work is anticipated to be required, including but not limited to: Removal of existing control panel; rerouting and re-terminating of audio cabling in the room to maintain working audio connections to the loudspeakers and existing-to-remain wall mounted analog I/O panel elsewhere in the room; Reducer plate/VESA mount adapter to fit over the existing wall box for a clean installation of the new control panel. Include programming cost for streamlined user control GUI of the in-room audio capabilities using the 15" GUI as the base programming. The owner at their discretion will add additional touch panels to selected event and/or meeting rooms based upon this itemized cost.

**END OF ADDENDUM #9**